

SECTION 071413 - HOT FLUID-APPLIED RUBBERIZED ASPHALT WATERPROOFING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Rubberized-asphalt waterproofing membrane, reinforced.
2. Molded-sheet drainage panels.
3. Insulation.
4. Plaza deck pavers.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Shop Drawings: Show locations and extent of waterproofing. Include details for substrate joints and cracks, sheet flashings, penetrations, inside and outside corners, tie-ins to adjoining waterproofing, and other termination conditions.

1.3 INFORMATIONAL SUBMITTALS

- A. Product test reports.
- B. Sample warranties.

1.4 QUALITY ASSURANCE

- A. Installer Qualifications: A firm that is approved or licensed by manufacturer for installation of waterproofing required for this Project and is eligible to receive special warranties specified.
- B. Preinstallation Conference: Conduct conference at Project site.

1.5 PROJECT CONDITIONS

- A. Environmental Limitations: Apply waterproofing within the range of ambient and substrate temperatures recommended by waterproofing manufacturer. Do not apply waterproofing to a damp or wet substrate, or when temperature is below 0 deg F.

1.6 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace waterproofing and sheet flashings that do not comply with requirements or that fail to remain watertight within specified warranty period.
 1. Warranty Period: 15 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 WATERPROOFING MEMBRANE

- A. Hot Fluid-Applied, Rubberized-Asphalt Waterproofing Membrane: Single component; 100 percent solids; hot fluid-applied, rubberized asphalt.
1. **Products:** Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to, the following:
 - a. **American Hydrotech, Inc.;** Monolithic Membrane 6125.

2.2 FLASHING SHEET MATERIALS

- A. Elastomeric Flashing Sheet: 50-mil- minimum, uncured sheet neoprene as follows:
1. Tensile Strength: 1400 psi minimum; ASTM D 412, Die C.
 2. Elongation: 300 percent minimum; ASTM D 412.
 3. Tear Resistance: 125 psi minimum; ASTM D 624, Die C.
 4. Brittleness: Does not break at minus 30 deg F; ASTM D 2137.

2.3 AUXILIARY MATERIALS

- A. Primer: ASTM D 41, asphaltic primer.
- B. Elastomeric Sheet: 50-mil- minimum, uncured sheet neoprene as follows:
1. Tensile Strength: 1400 psi minimum; ASTM D 412, Die C.
 2. Elongation: 300 percent minimum; ASTM D 412.
 3. Tear Resistance: 125 psi minimum; ASTM D 624, Die C.
 4. Brittleness: Does not break at minus 30 deg F; ASTM D 2137.
- C. Metal Termination Bars: Manufacturer's standard, predrilled stainless-steel or aluminum termination bars; approximately 1 by 1/8 inch thick; with anchors.
- D. Sealants and Accessories: Manufacturer's recommended sealants and accessories.
- E. Reinforcing Fabric: Manufacturer's recommended, spun-bonded polyester fabric.
- F. Protection Course: Manufacturer's standard, 80- to 90-mil- thick, fiberglass-reinforced rubberized asphalt or modified bituminous sheet.

2.4 MOLDED-SHEET DRAINAGE PANELS

- A. Woven-Geotextile-Faced, Molded-Sheet Drainage Panel: Manufactured composite subsurface drainage panels consisting of a woven-geotextile facing with an apparent opening size not exceeding No. 40 sieve, laminated to one side without a polymeric film bonded to the other side of a studded, nonbiodegradable, molded-plastic-sheet drainage core, with a horizontal flow rate not less than 2.8 gpm/ft..

2.5 INSULATION

- A. Board Insulation: Extruded-polystyrene board insulation complying with ASTM C 578, square edged.
1. Type VII, 60-psi minimum compressive strength.
 2. Type V, 100-psi minimum compressive strength.

2.6 PLAZA DECK PAVERS

- A. Plaza Deck Pavers: Heavyweight, hydraulically pressed, concrete units, square edged, manufactured for use as plaza deck pavers; minimum compressive strength 6500 psi, ASTM C 140; absorption not greater than 5 percent, ASTM C 140; no breakage and maximum 1 percent mass loss when tested for freeze-thaw resistance according to ASTM C 67.
1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. [Hanover Architectural Products.](#)
 - b. [Hastings Pavement Company, LLC.](#)
 - c. [Roofblok Limited.](#)
 - d. [Sunny Brook Pressed Concrete.](#)
 - e. [Wausau Tile, Inc.; Terra-Paving Division.](#)
 - f. [Westile Roofing Products.](#)
 2. Thickness 2 inches.
 3. Face Size: As indicated.
 4. Color: As selected by Architect from manufacturer's full range.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Clean and prepare substrates according to manufacturer's written instructions. Provide clean, dust-free, and dry substrate for waterproofing application.
- B. Mask off adjoining surfaces not receiving waterproofing to prevent spillage and overspray affecting other construction.
- C. Close off deck drains and other deck penetrations to prevent spillage and migration of waterproofing fluids.
- D. Remove grease, oil, form-release agents, paints, curing compounds, and other penetrating contaminants or film-forming coatings from concrete.
- E. Remove fins, ridges, and other projections and fill honeycomb, aggregate pockets, and other voids.

3.2 JOINTS, CRACKS, AND TERMINATIONS

- A. Prepare and treat substrates to receive waterproofing membrane, including joints and cracks, deck drains, corners, and penetrations according to manufacturer's written instructions.
 - 1. Adhere strip of elastomeric sheet to substrate in a layer of hot rubberized asphalt. Extend elastomeric sheet a minimum of 6 inches on each side of moving joints and cracks or joints and cracks exceeding 1/8 inch thick, and beyond deck drains and penetrations. Apply second layer of hot fluid-applied, rubberized asphalt over elastomeric sheet.
 - 2. Embed strip of reinforcing fabric into a layer of hot rubberized asphalt. Extend reinforcing fabric a minimum of 6 inches on each side of nonmoving joints and cracks not exceeding 1/8 inch thick, and beyond roof drains and penetrations.

- B. At expansion joints and discontinuous deck-to-wall or deck-to-deck joints, bridge joints with elastomeric sheet extended a minimum of 6 inches on each side of joints and adhere to substrates in a layer of hot rubberized asphalt. Apply second layer of hot fluid-applied, rubberized asphalt over elastomeric sheet.

3.3 FLASHING INSTALLATION

- A. Install elastomeric flashing sheets at terminations of waterproofing membrane according to manufacturer's written instructions.

3.4 MEMBRANE APPLICATION

- A. Apply primer, at manufacturer's recommended rate, over prepared substrate and allow to dry.
- B. Heat and apply rubberized asphalt according to manufacturer's written instructions.
- C. Reinforced Membrane: Apply hot rubberized asphalt to substrates and adjoining surfaces indicated. Spread to a thickness of 90 mils; embed reinforcing fabric, overlapping sheets 2 inches; spread another 125-mil- thick layer to provide a uniform, reinforced, seamless membrane 215 mils thick.
- D. Apply waterproofing over prepared joints and up wall terminations and vertical surfaces to heights indicated or required by manufacturer.
- E. Cover waterproofing with protection course with overlapped joints.

3.5 MOLDED-SHEET DRAINAGE PANEL INSTALLATION

- A. Place and secure molded-sheet drainage panels, with geotextile facing away from wall or deck substrate according to manufacturer's written instructions. Use methods that do not penetrate waterproofing. Lap edges and ends of geotextile to maintain continuity. Protect installed molded-sheet drainage panels during subsequent construction.

1. For vertical applications, install protection course before installing drainage panels.

3.6 INSULATION INSTALLATION

- A. Install insulation over waterproofed surfaces according to manufacturer's written instructions.

3.7 PLAZA DECK PAVER INSTALLATION

- A. Install concrete pavers in locations indicated according to manufacturer's written instructions.
- B. Accurately install adjustable-height paver pedestals and accessories in locations and to elevations required. Adjust for final level and slope with shims.
- C. Loosely lay pavers on pedestals, maintaining a uniform open joint width. Tightly seat pavers against spacers to eliminate lateral movement or drift of paving assembly. Align joint patterns parallel in each direction.
- D. Install pavers to not vary more than 1/16 inch in elevation between adjacent pavers or more than 1/16 inch from surface plane elevation of individual paver.

3.8 CLEANING AND PROTECTION

- A. Protect waterproofing from damage and wear during remainder of construction period.
- B. Clean spillage and soiling from adjacent construction using cleaning agents and procedures recommended by manufacturer of affected construction.

END OF SECTION 071413