

**GENERAL REQUIREMENTS - Division 01**

DIVISION 01	SECTION	TITLE	REVISION DATE	REVISION HIGHLIGHTS	PREVIOUS VERSION
	ALL	All Sections	11.2019	For all Division 01 sections, including those not listed here, the following revisions have been made: header and footer updated; related documents language added; related sections language deleted; LEED requirements added; industry standards updated; manufacturers and product names updated.	
	01 1000	Summary	11.2019	1.3 I Administration of Project Web Site 1.10 C Reference to specific LEED sections 1.13 A or B Contractor's use of Project site for construction operations 1.13 D Requirement for submittal of a site utilization plan 1.14 A & B Requirement of 72 hours notice changed to 21 days 1.15 C Requirement of 72 hours notice changed to 21 days 1.15 E Tobacco-free campus requirement revised 1.15 F Controlled substances prohibition revised 1.15 H Requirement for Contractor's employee screening revised; follow UHPD requirements 1.16 C.3 Keynoting to include specification section numbers <i>and</i> titles.	1/29/2018
	01 2100	Allowances	7.2023	Added Elevator Cabs allowance to coordinate with 14 2400 Hydraulic Elevators	11.2019
	01 2200	Unit Prices	7.2023	Added Unit Price requests for Rock Excavation and Canopy Trees and Understory Trees	11.2019
	01 2500	Substitution Procedures	7.2023 11.2019	Made corrections to the request form Added substitution request form, referenced in 1.4 A.1, at end of Section	11.2019
	01 3100	Project Management and Coordination	11.2019	1.4 B.1 Added posting locations of key personnel contact info with options for project scope 1.6 C.3.a Conflict analysis using "Autodesk Navisworks or similar software." 1.6 C.3.a Editing note - option for scaling conflict analysis procedure to project scope 1.8 A "Use Project Web Site mutually agreed upon by the Owner, Architect, and Contractor . . ." 1.9 B.1 Requirement for preconstruction conference "no later than 15 days before commencement of construction." 1.9 B.3 Added agenda items: quality control plan, site logistics plan, and site specific safety plan. 1.9 C.1 Requirement to submit proposed dates, for Owner's approval, of preinstallation conferences 1.9 C.2 Requirement for submittal of list of preinstallaton conferences including relevant specifications section(s) 1.9 C.4 Requirement to advise Owner, Owner's Cx Authority, and Architect in advance of conference 1.9 C.5 Added agenda items for Owner's tobacco-free and controlled substance requirements and harassment policy 1.9 D Changed "Progress Meetings" to "Owner, Architect, Contractor Meetings"	1/29/2018
	01 3200	Construction Progress Documentation	1.2024	Edited text throughout to use the active voice wherever possible and clarify the party responsible for required actions 3.2.C.3 Updated design milestones to align with UH Design Review Process	11.2019
	01 4000	Quality Requirements	11.2019	1.3 C.2 Give the option of unified mockup being built	1/29/2018
	01 4529	Structural Testing Laboratory Services	11.2019	3.4 F.2.a Revisions to cold weather placement of concrete requirements	1/29/2018
	01 5000	Temporary Facilities and Controls	11.2019	3.3 L Provide options for temporary use of new elevators 3.4 K Provide for "protected" walkways, eliminate language suggesting means and methods	1/29/2018
	01 7413	Construction Waste Management and Disposal	11.2019	1.7 A Added option for waste management coordinator to also serve as LEED coordinator if accredited	1/29/2018
	01 8114	Sustainable Design Requirements - LEED v4 BD+C	11.2019	New section	None
	01 8116	Sustainable Design Requirements - LEED v4 ID+C	11.2019	New section	None