



**UNIVERSITY OF HOUSTON
Campus Facilities Planning Committee**

- | | | |
|----|--|------------------------------------|
| 1. | Project Number | P774800 |
| 2. | Project Name | Task Force Security Kiosks |
| 3. | Committee Date | January, 2011 |
| 4. | Requesting Department | Department of Public Safety |
| 5. | Contact Name & Phone Number | Malcolm Davis & 3-0580 |
| 6. | Presenter: | Malcolm Davis |
| 7. | Description of Request | General Information |

Project Overview

The Department of Public Safety is constructing elevated Security Kiosks in the campus perimeter student parking lots 4A, 9C, 12A. It is anticipated these will be staffed by UHDPS Security Officers from 7am until 11pm Monday through Friday.

Background Information:

The President Task Force on Safety and Security recommended that raised security kiosks be placed in select University student parking lots. Because the areas in which UH students feel the most vulnerable are the perimeter student parking lots these lots were selected for this added security feature. This recommendation was approved by the President.

Raised security kiosks will provide an elevated platform from which security officers can observe pedestrian/vehicle movement in the lot. The Kiosks will work in concert with UHDPS Dispatch and the University camera system.

At the September 2010 meeting the Campus Facilities Planning Committee approved locating kiosks in perimeter lots 4A, 9C and 12A. (See attached location map.)

Kiosk Description:

The Security Kiosks will consist of a 4ft x 6ft prefabricated guard booth elevated on a 6ft steel pedestal stand. The guard booth will have corner-to-corner glass, which will have a 360 degree line of sight. The Security Kiosk and pedestal stand will be mounted to a cast-in-place (CIP) concrete pad with concrete filled steel bollards protecting all four sides. HVAC will be located on top of the structure and screened from view.

Electrical, data and telephone utilities from adjacent and nearby UH facilities will tie into each Kiosk.

To increase visibility each Kiosk will be in Cougar Red and tie into University branding efforts.

- 8. **Proposed Start Date:** Utilities beginning in January 2011
Installation beginning in March 2011
- 9. **Project Duration:** 12 weeks
- 10. **Schematic Image:**



Attachments

